ANSWERD.IT › TAKEOFFAI

Pre-Bid Cost Estimate

AI-Powered Construction Estimating — Powered by TakeoffAI

Project Information

Field	Details
Project	40×60 Metal Building with Concrete Slab
Location	Brownwood, Texas 76801
Trade Type	General Construction
Estimate Date	March 26, 2026
Prepared By	TakeoffAI — answerd.it
Estimate Type	Pre-Bid / Conceptual

Scope of Work

Build a 40×60 metal building with concrete slab in Brownwood, Texas. Standard steel frame construction, 14-foot walls, 3 walk doors, 2 roll-up doors, basic electrical.

- **Building Footprint:** 2,400 sq ft (40 ft × 60 ft)
- **Wall Height:** 14 feet
- **Foundation:** 4" concrete slab with rebar
- **Doors:** 3 walk doors (3×7), 2 roll-up doors (10×10)
- **Electrical:** Basic panel + lighting circuit
- **Region:** West Texas (CCI multiplier: 0.92)

Line-Item Cost Estimate

#	Description	Qty	Unit	Unit Cost	Total
1	Site preparation & grading	2,400	sqft	$1.85	$4,440
2	Concrete slab — 4" with rebar	2,400	sqft	$8.50	$20,400
3	Steel frame & erection	2,400	sqft	$12.00	$28,800
4	Metal roof panels	2,400	sqft	$4.25	$10,200
5	Metal wall panels	1,960	sqft	$3.75	$7,350
6	Walk doors (3×7) — supply & install	3	EA	$850	$2,550

7	Roll-up doors (10×10) — supply & install	2	EA	$2,200	$4,400
8	Electrical — 200A panel + lighting	1	LS	$6,500	$6,500
9	Gutter & downspout system	200	LF	$8.50	$1,700
10	Fasteners, anchors & misc hardware	1	LS	$2,800	$2,800

Cost Summary

	Amount
Materials Subtotal	$56,840
Labor Subtotal	$32,300
Equipment & Misc	$4,800
Direct Cost Subtotal	**$93,940**
Regional CCI Adjustment (0.92 — West TX)	−$7,515
Adjusted Direct Cost	**$86,425**
Overhead (20%)	$17,285
Cost + Overhead	**$103,710**
Target Margin (12%)	$12,445
TOTAL BID PRICE	**$116,155**
Per square foot	*$48.40/sqft*

Assumptions & Exclusions

Included:

- All labor, materials, and equipment listed above
- Concrete slab with standard rebar grid
- Standard steel building package (manufacturer-supplied)
- Basic electrical panel and lighting circuits only

Excluded:

- Permits and engineering fees (est. $2,500–4,500 — customer to verify locally)
- Plumbing or HVAC of any kind

- Insulation (spray foam or blanket — add $8,000–14,000 if needed)
- Interior finish work, flooring, or paint
- Site utilities (water/sewer/power extension to site)
- Geotechnical / soil testing
- Abnormal site conditions or rock excavation

Confidence & Notes

> **Estimate Confidence: MEDIUM**
> This is a conceptual pre-bid estimate based on regional unit costs and standard productivity factors for West Texas. Final pricing should be validated with subcontractor quotes for concrete, steel erection, and electrical. Material pricing is subject to change — steel has ±8% volatility over 60-day periods.

How to Run a Live Estimate with TakeoffAI

Option 1 — Web UI (recommended for clients):

1. Open `http://localhost:3000` in your browser
2. Click the **Pre-Bid Estimate** tab
3. Describe your project in plain English
4. Enter your zip code and trade type
5. Adjust overhead % and margin % sliders
6. Click **Calculate Estimate**
7. Export the results as CSV or PDF

Option 2 — Direct API call (for developers/integrations):

```
POST http://localhost:8000/api/estimate
Content-Type: application/json

{
  "description": "Describe your project here...",
  "zip_code": "76801",
  "trade_type": "General",
  "overhead_pct": 20,
  "margin_pct": 12
}
```

Option 3 — Terminal (quick test):

```
curl -s -X POST http://localhost:8000/api/estimate \
  -H "Content-Type: application/json" \
  -d '{"description":"Your project","zip_code":"76801",
       "trade_type":"General","overhead_pct":20,"margin_pct":12}'
```

About TakeoffAI

TakeoffAI is an AI-powered construction pre-bid estimation and bid-winning strategy system built by **answerd.it**. It uses Claude (Anthropic) to parse project descriptions, extract quantities, apply regional cost data, and generate professional line-item estimates in seconds — without spreadsheets.

- **GitHub:** github.com/answerdit/TakeoffAI
- **Built by:** answerd.it
- **Powered by:** Claude AI (Anthropic)
- **Version:** 1.0 — March 2026

This estimate was generated by TakeoffAI for demonstration and client-sharing purposes. All costs are estimates and should be verified with current market pricing before submitting a formal bid.